627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

SPONSOR: Interra USA, Inc.

900 SW 16th Street, Suite 125, Renton, WA 98057

Sound Transmission Loss RALTM-TL24-554

CONDUCTED: 2024-12-05

Page 1 of 13

ON: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum

Board each side

TEST METHODOLOGY

Riverbank Acoustical LaboratoriesTM is accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) as an ISO 17025:2017 Laboratory (NVLAP Lab Code: 100227-0) and for this test procedure. The test reported in this document conformed explicitly with ASTM E90-09 (2016): "Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements." The single number rating of the specimen was calculated according to ASTM E413-22: "Classification for Rating Sound Insulation." A description of the measurement procedure and room specifications is available upon request. The transmission loss values are for a single direction of measurement. The results presented in this report apply to the sample as received from the test sponsor.

SPECIMEN MEASUREMENTS & TEST CONDITIONS

The test specimen was designated by the sponsor as Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side. The building contractor (Seth Priser) and RAL staff compiled a detailed construction specification as follows:

Tracks (Top & Bottom)

Material: 25g EQ tracks

Dimensions: 2 tracks @ 2445 mm (96.25 in.) wide by 32 mm (1.25 in.) high

Depth: 92 mm (3.625 in.) Steel Thickness: 0.4 mm (0.01585 in.)

Installation: Friction fit over foam sill sealer

Overall Weight: 2.38 kg (5.25 lbs)
Mass per Unit Length: 0.49 kg/m (0.33 lbs/ft)



627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104

Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 2 of 13

Interra USA, Inc. 2024-12-05

SPECIMEN MEASUREMENTS & TEST CONDITIONS (continued)

Studs

Material: 25g EQ studs

Dimensions: 5 studs @ 32 mm (1.25 in.) wide by 2750 mm (108.25 in.) high

Depth: 92 mm (3.625 in.) Steel Thickness: 0.4 mm (0.01575 in.)

Stud Spacing: Studs spaced 610 mm (24 in.) on center

Installation: Side studs each fastened to test frame at midpoint with 1 screw each

Studs double crimped to top and bottom tracks at each connection point

Fasteners: Type W bugle head drywall screws

Overall Weight: 6.92 kg (15.25 lbs)
Mass per Unit Length: 0.50 kg/m (0.34 lbs/ft)

Note: A bead of acoustical sealant was used to seal the source side of the specimen where framing members

met the test frame (0.91 kg (2 lbs) total).

Insulation

Material: R-13 unfaced fiberglass

Dimensions: 4 pieces @ 610 mm (24 in.) wide by 2438 mm (96 in.) high

4 pieces @ 610 mm (24 in.) wide by 305 mm (12 in.) high

Depth: 92 mm (3.625 in.)

Installation: Friction fit between studs

Overall Weight: 6.8 kg (15 lbs)

Mass per Unit Volume: 11.05 kg/m³ (0.69 lbs/ft³)

Source Room Side

Material: Type X gypsum board

Dimensions: 2 panels @ 1219 mm (48 in.) wide by 2743 mm (108 in.) high

Thickness: 16 mm (0.625 in.)

Installation: Panels installed vertically and fastened to studs with screws Fasteners: Type S bugle head drywall screws, length @ 32 mm (1.25 in.)

Fastener Spacing: 406 mm (16 in.) on center Overall Weight: 73.71 kg (162.5 lbs) Mass Per Unit Area: 11.02 kg/m² (2.26 lbs/ft²)



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 3 of 13

Interra USA, Inc. 2024-12-05

SPECIMEN MEASUREMENTS & TEST CONDITIONS (continued)

Receive Room Side

Material: Type X gypsum board

Dimensions: 1 panel @ 1219 mm (48 in.) wide by 2743 mm (108 in.) high

2 panels @ 610 mm (24 in.) wide by 2743 mm (108 in.) high

Thickness: 16 mm (0.625 in.)

Installation: Panels installed vertically, fastened to study with screws

Panel joints staggered from source side panel joints

Fasteners: Type S bugle head drywall screws, length @ 32 mm (1.25 in.)

Fastener Spacing: 406 mm (16 in.) on center Overall Weight: 73.37 kg (161.75 lbs) Mass Per Unit Area: 10.97 kg/m² (2.25 lbs/ft²)

Note: Joints between gypsum board panels, and screw heads on both sides of the partition were treated with a

thin bead of acoustical sealant and metal tape (0.23 kg (0.5 lbs) total).



627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104

Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554

Page 4 of 13

Interra USA, Inc. 2024-12-05

SPECIMEN MEASUREMENTS & TEST CONDITIONS (continued)

Overall Specimen Measurements

Dimensions: 2.44 m (96.0 in) wide by 2.74 m (108.0 in) high

Thickness: 0.12 m (4.875 in) Weight: 164.31 kg (362.25 lbs) Overall Area: 6.689 m² (72. ft²)

Mass per Unit Area: 24.56 kg/m² (5.03 lbs/ft²)

Test Aperture

Opening Size: 2.74 m (9.0 ft.) by 4.27 m (14.0 ft.)

Filler Wall: Yes

Aperture Size: 2.44 m (96.0 in) wide by 2.74 m (108.0 in) high

Transmission Area: 6.689 m² (72. ft²)

Sealed: Entire periphery (both sides) with dense mastic

Test Environment

Source Room

Volume: 177.11 m³

Temperature: $20.6 \, ^{\circ}\text{C} \pm 0.0 \, ^{\circ}\text{C}$ Relative Humidity: $52.0 \% \pm 0.0 \%$

Receive Room

Volume: 178.33 m³

Temperature: $21.1 \, ^{\circ}\text{C} \pm 0.0 \, ^{\circ}\text{C}$ Relative Humidity: $49.5 \% \pm 1.0 \%$

Requirements

Temperature: 22° C +/- 2° C, not more than 3° C change over all tests. Relative Humidity: $\geq 30\%$, not more than +/- 3% change over all tests.



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE RALTM-TL24-554

Page 5 of 13

Interra USA, Inc. 2024-12-05



Figure 1 – Specimen mounted in test aperture, as viewed from source room



Figure 2 – Specimen mounted in test aperture, as viewed from receive room



RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE RALTM-TL24-554

Page 6 of 13

Interra USA, Inc. 2024-12-05




Figure 3 – Tracks and studs installed in test aperture



Figure 4 – Detail of stud double crimped to track



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE RALTM-TL24-554

Page 7 of 13

Interra USA, Inc. 2024-12-05



Figure 5 – Detail of side stud fastened to test frame



Figure 6 – Insulation installed in stud cavities



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 8 of 13

Interra USA, Inc. 2024-12-05

TEST RESULTS

Sound transmission loss values are tabulated at the eighteen standard frequency bands. A graphic presentation of the data and additional information appear on the following pages. The precision of the transmission loss test data is within the limits set by the ASTM Standard E90-09 (2016). See Appendix A for identification of corrections applied to the reported data.

FREQ.	<u>TL</u>	ΔTL	DEF.	FREQ.	<u>TL</u>	ΔTL	<u>DEF.</u>
100	18	0.50	0	800	58	0.15	0
125	29	0.31	6	1000	60	0.09	0
160	34	0.36	4	1250	62	0.13	0
200	38	0.43	3	1600	59	0.09	0
250	42	0.37	2	2000	50	0.07	5
315	46	0.18	1	2500	49	0.07	6
400	49	0.18	1	3150	53	0.07	2
500	52	0.15	0	4000	56	0.06	0
630	55	0.19	0	5000	59	0.13	0

STC=51

ABBREVIATION INDEX

FREQ. = 1/3 OCTAVE BAND CENTER FREQUENCY, Hz

TL = TRANSMISSION LOSS, dB

 $\Delta TL = 95\%$ CONFIDENCE INTERVAL FOR TL MEASUREMENTS, dB

DEF. = DEFICIENCIES, dB BELOW SHIFTED STC CONTOUR (SUM OF DEF = 30)

STC = SOUND TRANSMISSION CLASS

Tested by

Marc Sciaky

Senior Experimentalist

Report by

Keith Kimberling

Test Engineer

Approved by

Eric P. Wolfram

Laboratory Manager



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE


RALTM-TL24-554

Page 9 of 13

Interra USA, Inc. 2024-12-05

SOUND TRANSMISSION REPORT

Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side



STC=51 OITC=28

TRANSMISSION LOSS
SOUND TRANSMISSION CLASS CONTOUR



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 10 of 13

Interra USA, Inc. 2024-12-05

APPENDIX A: Extended Frequency Range Data

Specimen: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side (See Full Report)

The following non-accredited data were obtained in accordance with ASTM E90-09 (2016), but extend beyond the defined frequency range of 100Hz to 5,000Hz. These unofficial results are representative of the RAL test environment only and intended for research & comparison purposes. Sampling precision observed during this procedure is reported below. Corrections are detailed in Appendix B.

1/3 Octave Band	Sound			
Center Frequency	Transmission Loss	Applicable	ΔTL (Eq. A2.5)	Repeatability
(Hz)	(dB)	Corrections	(dB)	(dB)
21.5	20		1.00	
31.5	20	ZZ F	1.09	1.01
40	22	Z F	0.98	2.26
50	14		0.63	1.52
63	12		0.63	1.47
80	10		0.37	0.60
100	18		0.50	0.67
125	29		0.31	0.71
160	34		0.36	0.35
200	38		0.43	0.33
250	42		0.37	0.42
315	46		0.18	0.41
400	49		0.18	0.46
500	52		0.15	0.18
630	55		0.19	0.26
800	58		0.15	0.24
1000	60		0.09	0.27
1250	62		0.13	0.15
1600	59		0.09	0.12
2000	50		0.07	0.13
2500	49		0.07	0.19
3150	53		0.07	0.14
4000	56		0.06	0.17
5000	59		0.13	0.17
6300	62		0.22	0.21
8000	64	Z	0.19	0.50
10000	62	Z F	0.16	1.21
12500	57	Z F	0.11	1.74



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 11 of 13

Interra USA, Inc. 2024-12-05

APPENDIX B: Glossary of Standardized Corrections and Adjustments

Specimen: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side (See Full Report)

Mark Interpretation

- A Measured sound pressure levels in the receive room are within 10 dB of the ambient noise level at the marked frequency band. Receive room levels used to calculate Transmission Loss are corrected according to ASTM E90 Section 10.3.
- Measured sound pressure levels in the receive room are within 5 dB of the ambient noise level at the marked frequency band. Receive room levels used to calculate Transmission Loss are corrected according to ASTM E90 Section 10.3.1. Transmission Loss values calculated from levels corrected this way will be less than or equal to Transmission Loss values from a hypothetical test using the same specimen and a receive room with idealized ambient sound levels of (-\infty) dB.
- F The reported Transmission Loss is within 10 dB of the laboratory flanking limit at the marked frequency band. The measured performance of the specimen may be limited by the performance of the laboratory building structure at this frequency band.
- Z The reported Transmission Loss at the marked frequency band has been corrected according to ASTM E90 Section A3.2.7 to account for possible sound transmission through the filler assembly.
- The reported Transmission Loss at the marked frequency band has been corrected according to ASTM E90 Section A3.2.8 to account for possible sound transmission through the filler assembly. Transmission Loss values corrected this way will be less than or equal to Transmission Loss values from a hypothetical test using the same specimen and an idealized filler assembly with a Sound Transmission Class rating of (∞) .

APPENDIX C: Glossary of Variability Metrics

Specimen: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side (See Full Report)

ΔTL, the 95% confidence interval for reported transmission loss values, is calculated from the standard deviation of the sets of measurements for source room sound pressure level, receive room sound pressure level, and receive room sound absorption. This metric is calculated in an effort to quantify the combined influences of room geometry, microphone positioning, and other varying environmental conditions on reported results.

Repeatability, expressed as a 95% confidence interval, is calculated from the standard deviation of transmission loss as obtained from a set of six (6) consecutive tests conducted according to this test method by RAL on 2020-02-13. The tests were performed on a specimen composed of 24 gauge steel paneling, using the same test opening as used in this report. This metric provides an estimate of the variation in results that might be observed if the test were repeated with no change to the installed specimen. Note that repeatability will vary with the construction type.



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 12 of 13

Interra USA, Inc. 2024-12-05

APPENDIX D: Determination of Outdoor Indoor Transmission Class (OITC)

Specimen: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side (See Full Report)

The determination of the Outdoor Indoor Transmission Class (OITC) as reported below was made with explicit conformity to the procedures described in the ASTM E1332-22 test standard. Test Method ASTM E90-09 (2016) was used to obtain the sound transmission loss data. This rating is based on an average transportation noise source spectrum and an A-weighted sound level reduction, either of which may be inappropriate for some applications.

One-third Octave Band	Reference Sound Spectrum,	Test Specimen	
Center Frequency, Hz	dB	Transmission Loss, dB	
80	103	10	
100	102	18	
125	101	29	
160	98	34	
200	97	38	
250	95	42	
315	94	46	
400	93	49	
500	93	52	
630	91	55	
800	90	58	
1000	89	60	
1250	89	62	
1600	88	59	
2000	88	50	
2500	87	49	
3150	85	53	
4000	84	56	

OITC = 28



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

627 RIVERBANK DRIVE GENEVA, IL 60134 630-232-0104 Test Report

www.riverbankacoustics.com

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL24-554
Page 13 of 13

Interra USA, Inc. 2024-12-05

APPENDIX E: Instruments of Traceability

Specimen: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side (See Full Report)

		Serial	Date of	Calibration
Description	Model	Number	Certification	Due
System 2	3160-A-042	3160- 106968	2024-07-19	2025-07-19
Bruel & Kjaer Mic And Preamp C	Type 4943-B-001	2311439	2024-03-29	2025-03-29
Bruel & Kjaer Pistonphone	Type 4228	2781248	2024-07-19	2025-07-19
EXTECH Hygro 663	SD700	A083663	2023-12-28	2024-12-28
EXTECH Hygro 6015	SD700	A.116015	2024-06-05	2025-06-05

APPENDIX F: Revisions to Original Test Report

Specimen: Baseline 25ga. Eq. Steel Stud Wall 24"oc - R-13 Insulation - Single Layer 5/8" Type- X Gypsum Board each side (See Full Report)

<u>Date</u>	Revision		
2024-12-19	Original report issued		

END



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.